EXISTING

Remove 18m of Resident Permit Holder parking bay (approx. 3 spaces).

Cycle Hire Station

SCALA STREET

CHARLOTTE STREET

WHITFIELD STREET

Remove 2.4m of paid for parking bay.

Remove 21.4m of Resident Permit Holder parking bay and relocate (approx. 4 spaces).

Remove 7m of Resident Permit Holder parking bay (approx.1.5 spaces).

Remove 26m of Double Yellow Lines.

PROPOSED

Proposed continuous footway.

Convert existing Resident Permit Holder parking bay (18m) to E-scooter bay and 1 Bikehangar.

Proposed footway buildouts, trees and benches

Proposed hopscotch

Cycle Hire Station

SCALA STREET

E-SCOOTER & CYCLE HIRE

CHARLOTTE STREET

WHITFIELD STREET

Except cycles

Proposed one-way operation on Scala Street.

Proposed footway buildout.

Existing paid for parking bay to be shortened to 10m (approx. 2 spaces).

Proposed 'No Loading' and No Waiting' restrictions.

Relocated 25m of Resident Permit Holder parking bay (approx. 5 spaces).

KEY

- Items to be removed
- Existing road marking
- Existing carriageway
- Existing tree
- Existing utility cover (to be adjusted)
- Proposed road marking (white)
- Proposed road marking (yellow)
- Existing footway
- Proposed footway paving slabs
- Proposed asphalt surfacing
- Proposed granite setts
- Proposed permeable paving
- Proposed green area (subject to trial hole investigation)
- Proposed tree (indicative location, subject to trial hole investigation)
- Proposed bench
- Proposed full height kerb
- Proposed edging
- Proposed dropped kerb
- Proposed dropper kerb
- Proposed entry kerb
- Proposed red tactile paving
- Proposed buff tactile paving
- Proposed bikehangar

Rev	By	Date	Amendments

Camden

Design Team
Transport Strategy Service
London Borough of Camden
5 Pancras Square
Tel 020 7974 5551, Fax 020 7974 6952
DX 2106 Euston, Minicom 020 7974 6866

Project
FITZROVIA PHASE 2

Drawing Title
CONSULTATION PLAN
SCALA STREET

Scale: NTS @ A3	Date: FEB 2026
Drawn By: JC	File Ref: -
Checked By: AC / RC	Dwg Name
Drawing Location: -	
Drawing Number: FitzroviaPh2-ScalaSt-CON-01	Rev. -